

LABORATORY :- MOXLEY INDUSTRIAL CENTRE, WESTERN WAY,
ADDRESS WEDNESBURY, WEST MIDLANDS, WS10 7BG
TEL: 0121 505 4050 FAX: 0121 505 1115
www.rotechlabs.co.uk info@rotechlabs.co.uk

Test Report

Our Ref: GBW Number 131332 Issue 1 Date 13/01/2015 Page 1 of 1

A/C No: M114

Tested For:- T I MIDWOOD & COMPANY LIMITED
Green Lane
Wardle
Nantwich
Cheshire
CW5 6BJ

SALT SPRAY TESTING OF TIMCO DRYWALL SCREW SAMPLES

INTRODUCTION

The finished samples were submitted to the laboratory for Salt Spray Corrosion Resistance Testing in accordance with the relevant specification.

RELEVANT INFORMATION

Description: 6 off. Timco Drywall Screw Samples
Finish: Zinc / Yellow Passivated Coating
Specification: Salt Spray Test in accordance with ASTM B117-11
Test Duration: 100 Hours Salt Spray Exposure
Submitted By: Peter Owen
Customer's Order No: 5175
Sample Receipt Date: 07/01/2015

RESULTS

Salt Spray Test (ASTM B117-11)

The samples showed no evidence of red ferrous corrosion after 100 hours exposure.

CONCLUSION

The finish applied to the Timco Drywall Screw Samples (Zinc / Yellow Passivated Coating) tested, withstood 100 hours Salt Spray Test without the formation of red ferrous corrosion.

REPORT COMPILED BY



G B Withers
Corrosion Science
Technician

REPORT APPROVED BY



G B Withers
Corrosion Science
Technician

TESTS MARKED "NOT UKAS ACCREDITED" IN THIS REPORT/CERTIFICATE ARE NOT INCLUDED IN THE UKAS ACCREDITATION SCHEDULE FOR OUR LABORATORY.
TESTS MARKED 'SC' HAVE BEEN SUBCONTRACTED.
OPINIONS AND INTERPRETATIONS EXPRESSED HEREIN ARE OUTSIDE THE SCOPE OF UKAS ACCREDITATION.
THIS TEST REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL, WITHOUT WRITTEN APPROVAL OF THE LABORATORY.
RESULTS IN THIS REPORT RELATE ONLY TO THE ITEMS TESTED.